BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2018-19 Dated: 27-02-2019

APPROVED TENDER SCHEDULE –'B'

Item-78

Name of Work:-Construction of CC drain at B sector Main road in ward no 04, Yelahanka Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri MOHIT GOWDA G	
				Rate	Rate in Words
1	Earthwork in execavation for foundation of structure like culverts, retaining wall etc., as per drawing and technical specification, including setting out, construction of shoring and bracing, dressing of sides and bottom, back filling with approved material, disposal of balance earth as per specification, including cost of labour, HOM etc., complete. In all kinds of soil by manual means. (P.No.256, I.No.34.15.1 of PW,P&IWTD S.R 2018-19)	Cum	121.5	150.00	Rupees One Hundred Fifty Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	Cum	121.5	85.00	Rupees Eighty Five Only
3	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications, MORTH specifications No. 408, (P.No.13, I.No.4-1.2 of PW,P&IWTD S.R 2018-19)	Cum	19.35	4000.00	Rupees Four Thousand Only
4	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 265 Ite mo 37.59.2 SR 2018-19	Cum	41.76	6000.00	Rupees Six Thousand Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri MOHIT GOWDA G	
				Rate	Rate in Words
5	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19)	Tonns	2.8	65000.00	Rupees Sixty Five Thousand Only
6	Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.	Sqm	7.2	5500.00	Rupees Five Thousand Five Hundred Only
7	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.	Sqm	90	2000.00	Rupees Two Thousand Only

Signature of the Contractor

Executive Engineer
Yelahanka Division,
BBMP, Bengaluru-64.

Executive Engineer
Yelahanka Division
Yelahanka ZONE
Bruhat Bangalore Mahanagara Palike
BANGALORE 560064